



## **Asbestos Management Survey Report**



***Taihape Hospital, Main Maternity Building  
Interior Asbestos Assessment.***

## Report Production

Survey Conducted by: Haretini Wakefield  
Date of Survey: 16<sup>th</sup> of March 2018  
Position in Company: Operations Project Manager  
Assessor Number: AA18020017  
Expiry Date: 9 February 2023  
Signature: *H. Wakefield*

Survey Prepared by: Ali Lind  
Date Survey Prepared: 26<sup>th</sup> of March 2018  
Position in Company: Operations Project Manager  
Assessor Number: AA17090140  
Expiry Date: 5 September 2022  
Signature: *Ali Lind*

Survey Prepared by: Bruce Wakefield  
Date Survey Prepared: 02<sup>nd</sup> of April 2018  
Position in Company: Managing Director  
Assessor Number: AA16090111  
Expiry Date: 5 September 2021  
Signature: *B. Wakefield*

## **Contents Page**

### **Section 1**

- **Report Details**
- **Introduction**
- **Survey Methodology**
- **General Recommendations for Asbestos Cement Products**
- **General Recommendation for Asbestos Insulation, Coatings or Insulating Board (AIB)**
- **Survey Summary & Recommendations**
- **Risk Assessment Methods**

### **Section 2**

- **Identification & Photographic Register Sheets**
- **Survey Recommendations**
- **Survey Record Sheets**
- **Laboratory Certificate of Analysis**
- **Management Inspection Record**

## **Introduction**

**Further to an invitation from Mr. Grant Hood**

**(WDHB – Whanganui District Health Board.)**

**AISL - Asbestos Inspection Services Limited was requested to carry out a Management Survey at -**

**Taihape Hospital, Maternity Block. Interior Locations**

**There are 2 designated categories of Asbestos surveys currently available. These are listed below:**

### **Management Survey**

**Standard sampling, identification and assessment survey (Sampling Survey), the purpose of which is to locate as far as reasonably Practicable the presence and extent of any suspect asbestos containing materials in the building and their condition. This is done by the collection and analysis of samples of suspect asbestos containing materials.**

### **Refurbishment / Demolition Survey**

**Full access sampling and identification survey (Pre-demolition/Major Refurbishment Survey). This type of survey is used to locate and describe as far as reasonably practicable, all asbestos containing materials in the building and may involve destructive inspection as necessary to gain access to all areas, including those that may be difficult to reach. A full sampling programme is undertaken to identify possible asbestos containing materials and estimates of the volume and surface areas of asbestos containing materials made.**

**Access arrangements were made with aid of Mr. Grant Hood (Whanganui District Health Board) to ensure all accessible areas were surveyed during the project.**

**The survey was carried out on 16/03/2018 and completed 10 days thereafter.**

**The survey was to include for visual inspection within the above premises.**

**The survey was undertaken and completed by members of the AISL – Asbestos Inspection Services Limited survey team.**

**During the survey the building remained un-occupied.**

## **Disclaimer**

**Every effort has been made to identify all asbestos materials so far as was reasonably practicable to do so within the scope of the survey and the attached report. Methods used to carry out the survey were agreed with the client prior to any works being commenced.**

**Survey techniques used involves trained and experienced surveyors using the combined approach about visual examination. and bulk sample collections where required.**

**It is always possible after a survey that asbestos based materials may remain in the property or area covered by that survey, this could be due to several reasons:**

- Asbestos materials existing outside the scope of the survey.**
- Materials may be concealed or hidden by other items or covered surfaces i.e. paint, over boarding, concealing etc. Where this is the case then its discovery will be limited.**
- Asbestos may well be hidden as part of the structure to a building and not visible until the structure is demolished later.**
- Fragments from previous asbestos removal projects may well be present in various areas; general asbestos fragments do not form part of this survey however all good intentions are made for its discovery.**

**Where an area has been formerly stripped of asbestos i.e. plant rooms, ducts etc. and new coverings added, it must be pointed out that asbestos removal techniques have improved steadily over the years since its initial introduction. Most particularly would be the Health and Safety at Work (Asbestos) Regulations 2016, that outline enforceable strategies. Asbestos removal prior to this regulation would not be of today's standard and therefore fragments may be present beneath new coverings.**

**This survey will detail areas accessed and all samples taken, where an area is not covered by this survey it will be due to No Access for one reason or other i.e. working technicians, delicate location or just simply no admittance. It may have been necessary for the restrictions of the surveyor's specialist to be confirmed prior to the survey.**

**Admittance for the survey may be restricted for many reasons outside our control such as height, deadlines to others, steady complications or confined space. Where electrical equipment is present and presumed in the way of the survey no access will be attempted until proof of its safe state is given. Our operatives have a duty of care under the Health and Safety at Work Act (2016) for both themselves and others.**

## **Disclaimer**

**In the structure where asbestos has been located and not all zones have been examined, any material that is found to be suspicious and not detailed as part of the survey should be treated with caution and sampled accordingly.**

**Certain materials contain asbestos to variable grades and some may be less densely contaminated at certain locations (Artex for example). Where this is the case the sample taken may not be representative of the whole product throughout, therefore composite sampling is therefore encouraged.**

**Where a survey is carried out under the guidance of the owner of the property or his representative, then the survey will be as per his/her instructions and supervision at that time.**

**Asbestos Inspection Services Limited cannot accept any liability for loss, injury, damage or penalty issues due to errors or oversights contained within this report.**

**Asbestos Inspection Services Limited cannot be held responsible for any damage caused as part of this survey carried out on your behalf. Due to the landscape and stipulation of sampling for asbestos some danger is inevitable and will be limited to just that necessary for the taking of the sample.**

## **General Recommendations for Asbestos Cement Products.**

**Work with cement products containing asbestos is covered by the Management and Removal of Asbestos (November 2016) Approved Code of Practice.**

**An assessment of all proposed works which may disturb any asbestos should be carried out to launch the risk existing, the appropriate precautions must be adopted to control any exposure. This should combine the succeeding over-all principles:**

- **Where work on asbestos cement is inevitable, keep the materials wet during work and avoid breakage wherever possible. Acceptable PPE must be worn always.**
- **Avoid using power tools. If deemed necessary to use power tools set at the lowest possible speed, exhaust ventilation such as cowls must be fitted to power tool and utilising the “investigation technique” with high efficiency H type vacuum units.**
- **Organise the work in a single controlled location where practicable, to streamline control and supervision. Isolate working areas using warning signs and tape barriers, or in case of significant fibre levels by means of a sealed polythene work enclosure and negative pressure equipment. Air tests must also be carried out by an independent asbestos assessor.**
- **Signify respirator zones where the Control Limit is likely to be exceeded and ensure that all persons entering the zones wear appropriate RPE/PPE are trained in its use.**
- **Ensure that those persons employed in working on asbestos cement are suitably trained in the correct working practices, control methods and anticipation of risks.**
- **Keep the work area clean during the work and use methods that abate dust creation, avoid sweeping and brushing, which will make dust airborne.**
- **Dispose of asbestos cement waste safely as Asbestos Waste under the statutory consignment note procedures in accordance with the Health and Safety at Work (Asbestos) Regulations 2016.**
- **Avoid further disturbance of asbestos cement products wherever possible by relocating or re-routing facilities.**
- **Clearly identify and label any asbestos cement products.**

## **General Recommendations for Asbestos Insulation, Coatings or Insulating Board (AIB)**

Where the materials are in safe condition and the risk of disturbance is small, they can be maintained on site. They should be identified with adequate warning signs and routinely inspected for damages. All asbestos materials should not be drilled, abraded or disturbed in any way.

All asbestos containing materials should be removed prior to any planned refurbishment or demolition works, where damage is likely to be sustained during the occupant's activities or where future decline is likely.

Work on any of these items may only be carried out by a specialist contractor licensed under the Health & Safety at Work Act 2016. The selected contractor is required to notify the WSNZ at least 5 days prior to commencement of the works, and to provide a written Method Statement as follows:

- Full explanation of the works to be carried out and its duration.
- Type, quantity and location of asbestos to be removed.
- Anticipated exposure levels and persons affected.
- Enclosure construction details, layout and location, signage and ventilation.
- Protections to be adopted to minimize exposure to lowest possible level and to control release of asbestos fibre beyond the work area.
- Validation for any withdrawal from preferred methods, e.g. where wet stripping cannot be used.
- Type, use and decontamination of RPE/PPE
- Waste removal and disposal procedures
- Training and instruction of employees
- Emergency procedures on site



total risk score of between 0 and 12 is calculated using four categories that are evaluated by the surveyor against given values. The criteria and the respective values are as follows:

### **Product Type**

- 1 Asbestos reinforced composites such as plastics, resins, mastic, roofing felt, vinyl tiles, paints and decorative finishes, asbestos cement products.
- 2 Asbestos insulation board, mill boards, other low-density insulation boards, asbestos textiles, gaskets, ropes and woven textiles, asbestos paper and felt.
- 3 Thermal insulation (e.g. pipe and boiler lagging), sprayed asbestos, loose asbestos, asbestos mattresses and packing.

### **Condition/Extent of Damage**

- 0 Good condition, no visible damage.
- 1 Low damage, a few scratches or surface marks, broken edges on boards, tiles etc.
- 2 Medium damage, significant breakage of materials or several small areas where material has been damaged, revealing loose asbestos fibres.
- 3 High damage or delamination of materials, sprays and thermal insulation. Visible asbestos debris.

### **Surface Treatment**

- 0 Composite materials containing asbestos, such as reinforced plastics, resins, vinyl tiles.
- 1 Enclosed sprays and lagging, asbestos insulation board with exposed surface painted or encapsulated, asbestos cement products.
- 2 Unsealed asbestos insulation board or encapsulated lagging and sprays.
- 3 Unsealed lagging and sprays.

## Material Assessment Methods

## **Material Assessment Methods**

### **Asbestos Type**

- 1 Chrysotile (white) asbestos.**
- 2 Amosite (brown) asbestos.**
- 3 Crocidolite (blue) asbestos.**

The algorithms shown against each situation are added together to give a total material risk score, for conciseness, the register we have prepared contains only the total risk score rather than the component scores.

The total score for each situation can be broadly classified using the following bands:

### **Material Risk Score**

**0 - 3 Very Low Risk**

**4 - 6 Low Risk**

**7 – 9 Medium Risk**

**10 – 12 High Risk**

It is likely that high risk items will be highlighted in the report text and that some immediate action will be required.

Other items may also be measured for consideration where the decision of the surveyor recommends this would be beneficial.

## Priority Assessment Formula

A priority risk score of between 0 and 12 is calculated using four categories that are evaluated by the duty holder.

Although a surveyor may have some of the information which will contribute to the risk assessment and may be part of an assessment team, the duty holder is required to make a risk assessment based on the survey findings and their detailed knowledge of the activities carried out within the premises. The criteria and the respective values are as follows:

### Normal occupant activity

Assessment factor	Score	Examples of score variables
Main type of activity in area	0	Rare disturbance activity (e.g. little used store room)
	1	Low disturbance activities (e.g. office type activity)
	2	Periodic disturbance (e.g. industrial or vehicular activity which may contact ACMs)
	3	High levels of disturbance, (e.g. fire door with asbestos insulating board)
Secondary activities for area	As above	

## Priority Assessment Formula

### Likelihood of disturbance

Assessment factor	Score	Examples of score variables
Location	0	Outdoors
	1	Large rooms or well-ventilated areas
	2	Rooms up to 100 m <sup>2</sup>
	3	Confined spaces
Accessibility	0	Usually inaccessible or unlikely to be disturbed
	1	Occasionally likely to be disturbed
	2	Easily disturbed
	3	Routinely disturbed
Extent/amount	0	Small amounts or items (e.g. strings, gaskets)
	1	<10 m <sup>2</sup> or <10 m
	2	10 m <sup>2</sup> to 50 m <sup>2</sup> or 10 m to 50 m
	3	>50 m <sup>2</sup> or >50 m

### Human exposure potential

Assessment factor	Score	Examples of score variables
Number of occupants	0	None
	1	1 to 3
	2	4 to 10
	3	>10
Frequency of use of area	0	Infrequent
	1	Monthly
	2	Weekly
	3	Daily
Average time area is in use	0	<1 hour
	1	1 to 3 hours
	2	3 to 6 hours
	3	>6 hours

## Priority Assessment Formula

### Maintenance activity

Assessment factor	Score	Examples of score variables
Type of maintenance activity	0	Minor disturbance (e.g. possibility of contact when gaining access)
	1	Low disturbance (e.g. changing light bulbs in asbestos insulating board ceiling)
	2	Medium disturbance (e.g. lifting one or two asbestos insulating board ceiling tiles to access a valve)
	3	High levels of disturbance (e.g. removing many asbestos insulating board ceiling tiles to replace a valve or for re-cabling)
Frequency of maintenance activity	0	ACM unlikely to be disturbed for maintenance
	1	≤1 per year
	2	>1 per year
	3	>1 per month

The score for each variable is determined by calculating the average score of the appropriate factors.

The algorithms shown against each section are added together to give a total priority risk score, for conciseness, the register we have prepared contains only the overall risk score rather than the component scores.

### Priority Risk Score

0 - 3 Very Low Risk

4 - 6 Low Risk

7 – 9 Medium Risk

10 – 12 High Risk

## Overall Hazard Risk Assessment Formulae


The material and priority assessment scores provide an overall hazard risk score for each situation which can be broadly classified using the following table:

		Material Assessment			
		10-12	7-9	5-6	1-4
Priority Assessment	10-12				
	7-9				
	4-6				
	0-3				


Key		
	High Risk	Total score = 19-24
	Medium Risk	Total score = 13-18
	Low Risk	Total score = 7-12
	Very Low Risk	Total score = 1-6

Specific Locations that have been Analysed for asbestos based material's or Presumed to Contain Asbestos Containing material's.


**ID: CARD NO:030**

Photograph No.	DSCN0388	
Location/Area	Interior kitchen: Vinyl walls.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	76.6m2	


**ID: CARD NO:031**

Photograph No.	DSCN0389	
Location/Area	Interior Dining: Vinyl flooring.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	96.0m2	


**ID: CARD NO:032**

Photograph No.	DSCN0390	
Location/Area	Interior kitchen. Switchboard.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	1.03m2	

**ID: CARD NO:033**

Photograph No.	DSCN0391	
Location/Area	Interior kitchen toilets. Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	1.03m2	

**ID: CARD NO:034**

Photograph No.	DSCN0392	
Location/Area	Firecell 1, storeroom. Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	4.2m2	



**ID: CARD NO:035**

Photograph No.	DSCN0393
Location/Area	Firecell 1, storeroom entry. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	2.2m2

**ID: CARD NO:036**


Photograph No.	DSCN0394
Location/Area	Firecell 1, toilet. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	6.0m2

**ID: CARD NO:037**

Photograph No.	DSCN0395
Location/Area	Firecell 1, toilet. Vinyl walls.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	23.5m2

**ID: CARD NO:038**

Photograph No.	DSCN0396
Location/Area	Firecell 1, Oxygen room. Vinyl covering.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	1.05m2

**ID: CARD NO:039**

Photograph No.	DSCN0397
Location/Area	Firecell 1, changing room. Vinyl covering.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	8.0m2

**ID: CARD NO:040**

Photograph No.	DSCN0398
Location/Area	Firecell 1, medical records. Vinyl covering.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	8.0m2



**ID: CARD NO:041**


Photograph No.	DSCN0399
Location/Area	Firecell 1, patient room. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	16.1m2

**ID: CARD NO:042**

Photograph No.	DSCN0400
Location/Area	Firecell 1, patient room. (Blue speckled) Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	9.8m2

**ID: CARD NO:043**


Photograph No.	DSCN0401
Location/Area	Firecell 1, administration office fire door.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	3.2m2

**ID: CARD NO:044**


Photograph No.	DSCN0402
Location/Area	Firecell 1, kitchen. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	5.5m2

**ID: CARD NO:045**


Photograph No.	DSCN0403
Location/Area	Firecell 1, drug room. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	10.15m2

**ID: CARD NO:046**


Photograph No.	DSCN0404
Location/Area	Firecell 2, physio room. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	45.0m2




**ID: CARD NO:047**

Photograph No.	DSCN0405	
Location/Area	Firecell 2, physio room. (Blue speckled) Vinyl covering.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	13.2m2	


**ID: CARD NO:048**

Photograph No.	DSCN0406	
Location/Area	Firecell 2, medical 2. Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	12.9m2	


**ID: CARD NO:049**

Photograph No.	DSCN0407	
Location/Area	Firecell 2, medical 2. Vinyl walls.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	31.5m2	


**ID: CARD NO:050**

Photograph No.	DSCN0408	
Location/Area	Firecell 2, medical 2 toilets. Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	4.75m2	

**ID: CARD NO:051**

Photograph No.	DSCN0409	
Location/Area	Firecell 2, medical 3. Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	16.7m2	

**ID: CARD NO:052**

Photograph No.	DSCN0410	
Location/Area	Firecell 2, medical 3. Vinyl walls.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	12.4m2	

**ID: CARD NO:053**

Photograph No.	DSCN0411
Location/Area	Firecell 2, medical 3/4. Door.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	12.0m2

**ID: CARD NO:054**

Photograph No.	DSCN0412
Location/Area	Firecell 2, medical 4. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	16.7m2

**ID: CARD NO:055**

Photograph No.	DSCN0413
Location/Area	Firecell 2, medical 4. Vinyl walls.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	12.4m2

**ID: CARD NO:056**

Photograph No.	DSCN0414
Location/Area	Firecell 2, toilet 1. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	6.2m2

**ID: CARD NO:057**

Photograph No.	DSCN0415
Location/Area	Firecell 2, toilet 1. Vinyl walls.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	24.3m2

**ID: CARD NO:058**

Photograph No.	DSCN0416
Location/Area	Firecell 2, CC1. Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	45.2m2



**ID: CARD NO:059**

Photograph No.	DSCN0417
Location/Area	Firecell 2, CC1. Vinyl walls.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	19.6m2

**ID: CARD NO:060**

Photograph No.	DSCN0418
Location/Area	Firecell 2, CC1. Door.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	6.0m2

**ID: CARD NO:061**

Photograph No.	DSCN0419
Location/Area	Firecell 2, Disability toilet, Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	8.5m2

**ID: CARD NO:062**


Photograph No.	DSCN0420
Location/Area	Firecell 2, Disability toilet, Vinyl walls.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	64.0m2

**ID: CARD NO:063**


Photograph No.	DSCN0421
Location/Area	Firecell 2, Sluice room, Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	28.0m2

**ID: CARD NO:064**


Photograph No.	DSCN0422
Location/Area	Firecell 2, Sluice room (Doors), Vinyl floor.
Sample No.	Presumed the presence of ACM.
Laboratory Analysis Findings	Management Survey Only.
Quantity	8.0m2




**ID: CARD NO:065**

Photograph No.	DSCN0423	
Location/Area	Firecell 2, CC2, Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	45.2m2	


**ID: CARD NO:066**

Photograph No.	DSCN0424	
Location/Area	Firecell 2, CC2, Vinyl walls.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	19.6m2	


**ID: CARD NO:067**

Photograph No.	DSCN0425	
Location/Area	Firecell 2, CC2, Door.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	6.0m2	


**ID: CARD NO:068**

Photograph No.	DSCN0426	
Location/Area	Firecell 2, CC2, RH1/RH2 toilet. (vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	6.0m2	


**ID: CARD NO:069**

Photograph No.	DSCN0427	
Location/Area	Firecell 2, CC2, RH9/RH10 toilet. (vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	8.0m2	


**ID: CARD NO:070**

Photograph No.	DSCN0428	
Location/Area	Firecell 2, CC2, RH11/RH12 toilet. (vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	6.0m2	


**ID: CARD NO:071**

Photograph No.	DSCN0429	
Location/Area	Firecell 2, toilet 2. (vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	6.0m2	


**ID: CARD NO:072**

Photograph No.	DSCN0430	
Location/Area	Firecell 2, toilet 2. (vinyl walls).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	24.0m2	


**ID: CARD NO:073**

Photograph No.	DSCN0431	
Location/Area	Firecell 4, toilet 1. (vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	12.0m2	


**ID: CARD NO:074**

Photograph No.	DSCN0432	
Location/Area	Firecell 4, toilet 1. (vinyl walls).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	24.0m2	


**ID: CARD NO:075**

Photograph No.	DSCN0433	
Location/Area	Firecell 4, Shower. (vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	10.0m2	


**ID: CARD NO:076**

Photograph No.	DSCN0434	
Location/Area	Firecell 4, Shower. (vinyl walls).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	12.0m2	


**ID: CARD NO:077**

<b>Photograph No.</b>	DSCN0435	
<b>Location/Area</b>	Firecell 4, Disability Shower. (vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	3.0m2	


**ID: CARD NO:078**

<b>Photograph No.</b>	DSCN0436	
<b>Location/Area</b>	Firecell 4, Disability Shower. (vinyl walls).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	22.0m2	


**ID: CARD NO:079**

<b>Photograph No.</b>	DSCN0437	
<b>Location/Area</b>	Firecell 4, RH3/RH4 toilet. (vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	6.0m2	


**ID: CARD NO:080**

<b>Photograph No.</b>	DSCN0438	
<b>Location/Area</b>	Firecell 4, Switchboard.	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	2.0m2	

**ID: CARD NO:081**


<b>Photograph No.</b>	DSCN0439	
<b>Location/Area</b>	Firecell 4, toilet 2, Vinyl floor.	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	7.0m2	

**ID: CARD NO:082**

<b>Photograph No.</b>	DSCN0440	
<b>Location/Area</b>	Firecell 4, toilet 2, Vinyl walls.	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	20.0m2	




**ID: CARD NO:083**

Photograph No.	DSCN0441	
Location/Area	Firecell 4, Shute room, Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	2.0m2	


**ID: CARD NO:084**

Photograph No.	DSCN0442	Access Restricted.
Location/Area	Firecell 4, Linen room, Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	9.0m2	


**ID: CARD NO:085**

Photograph No.	DSCN0443	
Location/Area	Firecell 4, RH7/RH8 toilet, (Vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	5.0m2	


**ID: CARD NO:086**

Photograph No.	DSCN0444	
Location/Area	Firecell 5, Kitchen/Dining, (Vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	28.0m2	


**ID: CARD NO:087**

Photograph No.	DSCN0445	
Location/Area	Firecell 6, Rear stairs, (Vinyl floor).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	21.0m2	


**ID: CARD NO:088**

Photograph No.	DSCN0446	
Location/Area	Mortuary, Main switchboard.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	13.0m2	


**ID: CARD NO:089**

Photograph No.	DSCN0447	
Location/Area	Mortuary, Main switchboard. Vinyl covering.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	12.0m2	


**ID: CARD NO:090**

Photograph No.	DSCN0448	
Location/Area	Mortuary, Hallway. Vinyl floor.	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	25.0m2	


**ID: CARD NO:091**

Photograph No.	DSCN0449	
Location/Area	Mortuary, Telephone equipment. (Vinyl covering).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	7.0m2	


**ID: CARD NO:092**

Photograph No.	DSCN0450	
Location/Area	Mortuary, Toilet. (Vinyl covering).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	10.0m2	


**ID: CARD NO:093**

Photograph No.	DSCN0451	
Location/Area	Mortuary, Store room. (Vinyl covering).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	13.6m2	


**ID: CARD NO:094**

Photograph No.	DSCN0452	
Location/Area	Mortuary, Splint room. (Vinyl covering).	
Sample No.	Presumed the presence of ACM.	
Laboratory Analysis Findings	Management Survey Only.	
Quantity	13.8m2	


**ID: CARD NO:095**

<b>Photograph No.</b>	DSCN0453	
<b>Location/Area</b>	Mortuary, General store room. (Vinyl covering).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	11.0m2	

**ID: CARD NO:096**

<b>Photograph No.</b>	DSCN0454	
<b>Location/Area</b>	Mortuary, Clinic. (Vinyl covering).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	13.4m2	


**ID: CARD NO:097**

<b>Photograph No.</b>	DSCN0455	
<b>Location/Area</b>	Mortuary, Chiller. (Vinyl covering).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	9.9m2	


**ID: CARD NO:098**

<b>Photograph No.</b>	DSCN0456	Access Restricted
<b>Location/Area</b>	Mortuary, Medical records. (Vinyl covering).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	36.2m2	

**ID: CARD NO:099**

<b>Photograph No.</b>	DSCN0457	
<b>Location/Area</b>	Firecell 6, Ceiling entry, (Vinyl covering), (Lath & Plaster)	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	1.0m2	

**ID: CARD NO:100**

<b>Photograph No.</b>	DSCN0458	
<b>Location/Area</b>	Firecell 6, Whanau bathroom (Vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	5.4m2	

**ID: CARD NO:101**


<b>Photograph No.</b>	DSCN0459
<b>Location/Area</b>	Firecell 6, Whanau bathroom (Vinyl walls).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	9.8m2

**ID: CARD NO:102**

<b>Photograph No.</b>	DSCN0460
<b>Location/Area</b>	Firecell 6, Foyer (Vinyl floor).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	29.0m2

**ID: CARD NO:103**

<b>Photograph No.</b>	DSCN0461
<b>Location/Area</b>	Firecell 6, Clinical room (Vinyl floor).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	19.0m2

**ID: CARD NO:104**

<b>Photograph No.</b>	DSCN0462
<b>Location/Area</b>	Firecell 6, Clinical room 2 (Vinyl floor).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	13.2m2

**ID: CARD NO:105**

<b>Photograph No.</b>	DSCN0463
<b>Location/Area</b>	Firecell 6, Bathroom (Vinyl floor).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	7.5m2


**ID: CARD NO:106**

<b>Photograph No.</b>	DSCN0464
<b>Location/Area</b>	Firecell 6, Bathroom (Vinyl walls).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	22.5m2



**ID: CARD NO:107**

<b>Photograph No.</b>	DSCN0465
<b>Location/Area</b>	Firecell 6, Store lock (Vinyl floor).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	2.0m2

**ID: CARD NO:108**

<b>Photograph No.</b>	DSCN0466
<b>Location/Area</b>	Firecell 6, Birth unit (Vinyl floor).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	43.0m2

**ID: CARD NO:109**

<b>Photograph No.</b>	DSCN0467
<b>Location/Area</b>	Firecell 6, Birth unit bathroom (Vinyl floor).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	4.6m2

**ID: CARD NO:110**

<b>Photograph No.</b>	DSCN0468
<b>Location/Area</b>	Firecell 6, Birth unit bathroom (Vinyl walls).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	15.0m2

**ID: CARD NO:111**

<b>Photograph No.</b>	DSCN0469
<b>Location/Area</b>	Firecell 7, Switch board.
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	2.0m2

**ID: CARD NO:112**


<b>Photograph No.</b>	DSCN0470
<b>Location/Area</b>	Firecell 7, Switch board (vinyl covering).
<b>Sample No.</b>	Presumed the presence of ACM.
<b>Laboratory Analysis Findings</b>	Management Survey Only.
<b>Quantity</b>	1.45m2




**ID: CARD NO:113**

<b>Photograph No.</b>	DSCN0471	Access Restricted
<b>Location/Area</b>	Firecell 7, Store room (vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	4.6m2	


**ID: CARD NO:114**

<b>Photograph No.</b>	DSCN0472	
<b>Location/Area</b>	Firecell 7, Laundry (vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	35.0m2	


**ID: CARD NO:115**

<b>Photograph No.</b>	DSCN0473	
<b>Location/Area</b>	Firecell 7, Linen room (vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	7.2m2	


**ID: CARD NO:116**

<b>Photograph No.</b>	DSCN0474	
<b>Location/Area</b>	Firecell 7, Whanau room (vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	32.2m2	


**ID: CARD NO:117**

<b>Photograph No.</b>	DSCN0475	
<b>Location/Area</b>	Firecell 7, Whanau room toilets. (vinyl floor).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	2.1m2	


**ID: CARD NO:118**

<b>Photograph No.</b>	DSCN0476	
<b>Location/Area</b>	Firecell 7, Whanau room toilets. (vinyl walls).	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	10.9m2	


**ID: CARD NO:119**

<b>Photograph No.</b>	DSCN0477	
<b>Location/Area</b>	Sub-Floor: Joist packing	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	Quantity not recorded	

**ID: CARD NO:120**

<b>Photograph No.</b>	DSCN0478	
<b>Location/Area</b>	Sub-Floor: Pipe lagging	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	Quantity not recorded	

**ID: CARD NO:121**

<b>Photograph No.</b>	DSCN0479	
<b>Location/Area</b>	Sub-Floor: Suspect soil contamination	
<b>Sample No.</b>	Presumed the presence of ACM.	
<b>Laboratory Analysis Findings</b>	Management Survey Only.	
<b>Quantity</b>	Quantity not recorded	







## Inspection Personnel

**Taihape Hospital, Maternity Block.**

Date	Name	Company Name	Competency Attained	License No	Expiry Date	Phone Number	Email Address
16 <sup>th</sup> March 2018	Haretini Wakefield	Asbestos Inspection Services Limited	Licensed Asbestos Assessor	AA18020017	09 <sup>th</sup> of February 2023	+24 22 3234534	<a href="mailto:Haretini.wakefield@aisl.co.nz">Haretini.wakefield@aisl.co.nz</a>
16 <sup>th</sup> March 2018	Ali Lind	Asbestos Inspection Services Limited	Licensed Asbestos Assessor	AA17090140	05 <sup>th</sup> of September 2022	+24 27 8565624	<a href="mailto:Ali.lind@aisl.co.nz">Ali.lind@aisl.co.nz</a>
16 <sup>th</sup> March 2018	Bruce Wakefield	Asbestos Inspection Services Limited	Licensed Asbestos Assessor	AA16090111	05 <sup>th</sup> of September 2021	+64 27 7655123	<a href="mailto:Bruce.wakefield@aisl.co.nz">Bruce.wakefield@aisl.co.nz</a>



## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type: **Management Survey**

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
030	DSCN0388	Interior kitchen, Vinyl wall covering	Presumed	79.60m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
031	DSCN0389	Interior Dining Vinyl floor covering	Presumed	96.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
032	DSCN0390	Interior kitchen Switch board	Presumed	1.03m2	Suspected backing Board	Electrical board	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
033	DSCN0391	Interior kitchen toilet Vinyl floor covering	Presumed	8.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
034	DSCN0392	Firecell 1, Store room Vinyl floor covering	Presumed	4.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
035	DSCN0393	Firecell 1, Store room entry Vinyl floor covering	Presumed	2.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
036	DSCN0394	Firecell 1, toilet Vinyl floor covering	Presumed	6.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
037	DSCN0395	Firecell 1, toilet Vinyl wall covering	Presumed	23.50m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
038	DSCN0396	Firecell 1, Oxygen room Vinyl covering	Presumed	1.05m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
039	DSCN0397	Firecell 1, Changing room Vinyl covering	Presumed	8.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
040	DSCN0398	Firecell 1, Medical records Vinyl covering	Presumed	10.70m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.



## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type:

Management Survey

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action
041	DSCN0399	Firecell 1, Patient room Vinyl floor covering	Presumed	16.10m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
042	DSCN0400	Firecell 1, Patient room Vinyl floor covering	Presumed	9.80m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
043	DSCN0401	Firecell 1, Administration office Vinyl covering (Door)	Presumed	3.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
044	DSCN0402	Firecell 1, Kitchen Vinyl floor covering	Presumed	5.50m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
045	DSCN0403	Firecell 2, Drug room Vinyl floor covering	Presumed	10.13m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
046	DSCN0404	Firecell 2, Physio room. Vinyl floor covering.	Presumed	45.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
047	DSCN0405	Firecell 2, Physio room. Vinyl covering, (Speckled blue).	Presumed	13.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
048	DSCN0406	Firecell 2, Med 2. Vinyl floor covering.	Presumed	12.09m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
049	DSCN0407	Firecell 2, Med 2. Vinyl wall covering.	Presumed	31.72m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
050	DSCN0408	Firecell 2, Med 2. Toilet. Blue vinyl floor covering.	Presumed	4.75m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.



## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type:

**Management Survey**

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
051	DSCN0409	Firecell 2, Med 3. Vinyl floor covering.	Presumed	16.70m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
052	DSCN0410	Firecell 2, Med 3. Blue speckled vinyl wall covering.	Presumed	12.40m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
053	DSCN0411	Firecell 2, Med 3 & 4 Door. Blue speckled vinyl covering.	Presumed	12.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
054	DSCN0412	Firecell 2, Med 4. Vinyl floor covering.	Presumed	16.70m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
055	DSCN0413	Firecell 2, Med 4. Blue speckled vinyl wall covering.	Presumed	12.40m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
056	DSCN0414	Firecell 2, Toilet 1. Blue vinyl floor covering.	Presumed	6.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
057	DSCN0415	Firecell 2, Toilet 1. Blue speckled vinyl wall covering.	Presumed	24.30m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
058	DSCN0416	Firecell 2, CC1. Vinyl floor covering.	Presumed	45.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
059	DSCN0417	Firecell 2, CC1. Blue speckled vinyl wall covering.	Presumed	19.60m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
060	DSCN0418	Firecell 2, CC1. Blue speckled vinyl door covering.	Presumed	6.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.



## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type:

Management Survey

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
061	DSCN0419	Firecell 2, Disability toilets. Vinyl blue floor covering.	Presumed	8.50m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
062	DSCN0420	Firecell 2, Disability toilet. Blue vinyl wall covering.	Presumed	64.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
063	DSCN0421	Firecell 2, Sluice room. (Floor). Brown vinyl floor covering.	Presumed	28.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
064	DSCN0422	Firecell 2, Sluice room. (Door). Brown vinyl floor covering.	Presumed	8.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
065	DSCN0423	Firecell 2, CC2. Vinyl floor covering.	Presumed	45.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
066	DSCN0424	Firecell 2, CC2. Blue speckled vinyl wall covering.	Presumed	19.60m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
067	DSCN0425	Firecell 2, CC2. Blue speckled vinyl door covering	Presumed	6.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
068	DSCN0426	Firecell 2, RH1/RH2 Toilets. Vinyl floor covering.	Presumed	5.06m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
069	DSCN0427	Firecell 2, RH9/RH10. Toilets. Vinyl floor covering.	Presumed	8.06m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
070	DSCN0428	Firecell 2, RH11/RH12. Toilets. Vinyl floor covering.	Presumed	5.06m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.



## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type:

Management Survey

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
071	DSCN0429	Firecell 2, Toilet 2. Blue vinyl floor covering.	Presumed	5.50m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
072	DSCN0430	Firecell 2, Toilet 2. Blue speckled vinyl floor covering.	Presumed	24.10m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
073	DSCN0431	Firecell 4, Toilet 1. Blue vinyl floor covering.	Presumed	11.80m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
074	DSCN0432	Firecell 4, Toilet 1. Blue speckled vinyl wall covering.	Presumed	23.40m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
075	DSCN0433	Firecell 4, Shower. Blue vinyl floor	Presumed	10.60m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
076	DSCN0434	Firecell 4, Shower. vinyl wall	Presumed	12.70m2	Suspected backing Board.	Insulation board.	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
077	DSCN0435	Firecell 4, Disability shower. Vinyl floor	Presumed	2.70m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
078	DSCN0436	Firecell 4, Disability shower. vinyl wall	Presumed	72.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
079	DSCN0437	Firecell 4, RH3/4Toilets. Vinyl floor	Presumed	5.06m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
080	DSCN0438	Firecell 4, Switch-board.	Presumed	2.00m2	Suspected backing Board.	Insulation board.	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.



## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type:

Management Survey

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
081	DSCN0439	Firecell 4, Toilet 2. Blue vinyl floor	Presumed	6.80m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
082	DSCN0440	Firecell 4, Toilet 2. vinyl wall	Presumed	19.10m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
083	DSCN0441	Firecell 4, Shute room. Brown vinyl floor	Presumed	2.30m2	Suspected backing Board.	Insulation board.	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
084	DSCN0442	Firecell 4, Linen room. vinyl floor	Presumed	9.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
085	DSCN0443	Firecell 4, RH7/RH8 Toilets. Vinyl floor covering.	Presumed	5.04m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
086	DSCN0444	Firecell 5, Kitchen/dining. Vinyl floor covering.	Presumed	28.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
087	DSCN0445	Firecell 6, Rear staircase. Brown vinyl floor	Presumed	21.10m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
088	DSCN0446	Mortuary, Main Switch-board.	Presumed	13.20m2	Suspected backing Board.	Insulation board.	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
089	DSCN0447	Mortuary, Main Switch-board room. vinyl floor	Presumed	12.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
090	DSCN0448	Mortuary, Hallway. Brown vinyl floor covering.	Presumed	25.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.



## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type:

Management Survey

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
091	DSCN0449	Mortuary, Telephone equipment. Vinyl floor	Presumed	6.80m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
092	DSCN0450	Mortuary, Toilets. Orange vinyl floor covering.	Presumed	9.80m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
093	DSCN0451	Mortuary, Store room. Brown vinyl floor covering.	Presumed	13.60m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
094	DSCN0452	Mortuary, Splint room. Brown vinyl floor covering.	Presumed	13.80m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
095	DSCN0453	Mortuary, General store room. vinyl floor covering.	Presumed	11.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
096	DSCN0454	Mortuary, Clinic. Brown vinyl floor covering.	Presumed	13.40m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
097	DSCN0455	Mortuary, Chiller. Brown vinyl floor covering.	Presumed	9.90m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
098	DSCN0456	Mortuary, Medical records. Brown vinyl floor covering.	Presumed	36.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
099	DSCN0457	Firecell 6, Ceiling entry. Brown vinyl floor covering.	Presumed	1.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
100	DSCN0458	Firecell 6, Whanau bathroom. Marble vinyl floor covering.	Presumed	5.40m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.





## Survey Record Sheet

Ref: WDHB

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type:

Management Survey

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
101	DSCN0459	Firecell 6, Whanau bathroom. Brown vinyl wall covering.	Presumed	9.80m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
102	DSCN0460	Firecell 6, Foyer. Stone vinyl floor covering.	Presumed	29.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
103	DSCN0461	Firecell 6, Clinical room. Stone vinyl floor covering.	Presumed	19.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
104	DSCN0462	Firecell 6, Clinical room 2. Stone vinyl floor covering.	Presumed	13.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
105	DSCN0463	Firecell 6, Bathroom. Blue vinyl floor covering.	Presumed	7.50m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
106	DSCN0464	Firecell 6, Bathroom. Stone vinyl wall covering.	Presumed	22.50m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
107	DSCN0465	Firecell 6, Store Lock. Stone vinyl floor covering.	Presumed	2.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
108	DSCN0466	Firecell 6, Birth Unit. Stone vinyl floor covering.	Presumed	43.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
109	DSCN0467	Firecell 6, Birth Unit. Bathroom. Vinyl floor	Presumed	4.60m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
110	DSCN0468	Firecell 6, Birth unit bathroom (Vinyl walls).	Presumed	15.00m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.



## Survey Record Sheet

Site Address: Taihape Hospital, Taihape.

Date: 16/03/2018

Survey Type: **Management Survey**

ID Card No	Photo No	Location/Area Description	Sample Ref /Presumed	Quantity	Product Description	Asbestos Type	Product Type	Condition	Surface Treatment	Asbestos Type	Material Risk Score	Normal Occupant Activity	Likelihood of Disturbance	Human Exposure Potential	Maintenance Activity	Priority Risk Score	Overall Risk Score	Action	
111	DSCN0469	Firecell 7, Main Switch-board.	Presumed	2.00m2	Suspected backing Board.	Insulation board.	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
112	DSCN0470	Firecell 7, Switch-board cupboard. vinyl covering.	Presumed	1.45m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
113	DSCN0471	Firecell 7, Store room. Stone vinyl floor covering.	Presumed	4.60m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
114	DSCN0472	Firecell 7, Laundry. Stone vinyl floor covering.	Presumed	35.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
115	DSCN0473	Firecell 7, Linen room. Stone vinyl floor covering.	Presumed	7.20m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
116	DSCN0474	Firecell 7, Whanau room. Stone vinyl floor covering.	Presumed	32.0m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
117	DSCN0475	Firecell 7, Whanau room Toilets. vinyl floor covering.	Presumed	2.10m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
118	DSCN0476	Firecell 7, Whanau room Toilets. vinyl wall covering.	Presumed	10.90m2	Suspected vinyl or backing	Vinyl resin	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
119	DSCN0477	Sub-Floor: Joist packing	Presumed	Not recorded	Suspected ACM material.	Joist packer	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
120	DSCN0478	Sub-Floor: Pipe lagging	Presumed	Not recorded	Suspected ACM material	Pipe lagging Residue	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.
121	DSCN0479	Sub-Floor: Soil Contamination	Presumed	Not recorded	Suspected ACM debris	Soil Debris	1	0	0	1	0	0	0	0	0	0	0	Very low risk	Complete a Risk Assessment.